
A Line (Snelling) Bus Rapid Transit

April 22, 2014 Roseville Public Works, Environment & Transportation Commission






- Arterial BRT Overview
- A Line Concept Plans
 - Rosedale Transit Center
 - Snelling & County Road B
 - Snelling & Roselawn
- Next Steps
- Questions and Comments



12 corridors studied for arterial BRT




- Arterial Transitway Corridors Study completed April 2012
 - Developed
 Arterial BRT
 concept
 - Prioritized
 corridors for
 near-term
 implementation
 - Snelling (2015)
 - West 7th (2016)



• Limited Stop Service with Better Frequency

- BRT would become the primary route in the corridor, with increased service on evenings & weekends.
 - Stations would be sited about every 1/2 mile, compared to local stops every 1/8 mile.
 - Local bus would continue to run serve local trips and off-corridor branches.





Pre-Boarding Fare Payment

 For speedier boarding through all doors of the bus, BRT vehicles won't have on-board fareboxes.
 Customers will either purchase a ticket at the station or tap a Go-To card to pay fares.

Each station will have a ticket machine, where customers can buy tickets with cash or credit.



Customers with Go-To cards or passes can tap their card before boarding through any vehicle door.





Metro Transit police—not drivers will ensure customers have paid.



How will BRT be different?

• Neighborhood-Scale Stations with Amenities



Shelters



Waste bins



Ticket machines



Bike parking



NexTrip



Lighting



Snow removal



Maps & info



Security cameras



Radiant heat



Emergency phone

Stations will be equipped with more amenities for a safe and comfortable customer experience, similar to light rail.




G

Transit Signal Priority (TSP)

During rush hours today, local buses spend about 25% of their scheduled time stopped at red lights.

With transit signal priority buses can "ask" traffic signals for early or extended green lights to help buses keep moving.

As a BRT vehicle approaches an intersection, it will send a green request to the traffic signal, which chooses whether or not to lengthen a green light for BRT.




ALINE

• 2012-2013:

Advanced Planning & Concept Design

- 2014: Preliminary & Final Design Off-Corridor BRT Pilot Station Construction
- 2015: Construction
- Late 2015:
 Open for Revenue Service






a service of the Metropolitan Council

A Line (Snelling Avenue) BRT Corridor Design & Prototype Station Design **DRAFT 2014 MILESTONE SCHEDULE** 2014 S F Μ Μ Α Ν D J Α 0 **Design Input** Inventory, Survey, Site Investigation **PILOT STATION (7th & Olson, Minneapolis)** 50% design 90% design & final bid documents Bidding, award & construction **PROTOTYPICAL BRT SHELTER** Design input & concepts 50% design & Bid documents Bidding & award to manufacturer Shelter fabrication & installation at pilot site A LINE 30-50% design 90% design Final bid documents Review & major public outreach period

Current Activities

Ongoing: Project Outreach



July 2013, January 2014: Open Houses





January: 25 Business Owner Meetings


NEXT STEP: PRELIMINARY DESIGN OUTREACH

May 2014: Broad Outreach & Open Houses



Standard Station Concept

Ð




Roseville Stations



- Rosedale Transit
 Center
- Snelling & County Road B
- Snelling & Roselawn




Rosedale Transit Center



- Major employment / shopping connection
- Existing transit center anchoring 9 connecting bus routes
- A Line project would make minor modifications to transit center



Snelling & County Road B (Southbound)



Snelling & County Road B (Northbound)

- Accessible 80' platform in existing bus stop location
- **Small** shelter

EXIST. RIGHT-OF

MetroTransit


Station marker pylon / realtime information

EDGE OF PAVEMENT


FACE OF CURB

15'

Ticket vending machines



Snelling & Roselawn (Southbound)






- April-June 2014: Public outreach & compiling comments
- Summer 2014: Met Council action to define project scope
- October 2014: Final design
- March 2015: Construction contract award
- Spring-Fall 2015: Construction
- 4th Quarter 2015: Open for service



Future Lines



More information: *metrotransit.org/snelling-brt metrotransit.org/arterial-study*

Katie Roth, Senior Planner Arterial BRT Project Manager 612-349-7772 katie.roth@metrotransit.org



